

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE - 'B'

Name of Work:-Costruction of drains at Janatha Colony venkata in ward No-01 of Yelahanka Sub Division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB M200-24:- Dismantling of cement concrete pavement by mechanical means using pneumatic toos, breaking to pieces no exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 000 meters stacking serviceable and unserviceable materials separately complete as per specification MORTH specifications No 202 (P.No 138/ Item No 18.47)	Cum	47.07	843.48	Rupees eight hundred forty three and paise forty eight only
2	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	62.76	169.56	Rupees one hundred sixty nine and paise fifty six only
3	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	109.83	100.00	Rupees one hundred only
4	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	47.07	5256.36	Rupees five thousand two hundred fifty six and paise thirty six only

Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
			Rate	Rate in Words
5 Providing & laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal, coarse aggregated @ 0.69cum, and fine aggregated @ 0.460cum, with superplasticiser @ 3lts conforming to IS9103-1999 Reaffirmed -2008 machine mixed concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, bed blocks, anchor blocks, plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. specifications No.KBS 4.1,4.6 (P.No.13/ I.No.4.11)	Cum	31.38	6491.88 6249.32	Rupees six thousand four hundred ninety one and paise eighty eight only
6 Vacuum De- Watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery screed vibratory, Power floater, blade and disc etc., with all lead and lift (P 177/1.22.7	sqm	313.80	97.20	Rupees ninety seven and paise twenty only
7 Providing Groove cutting for width of 5mm to 10mm and epth 80mm to 100mm including cost of cutting machine geerator and HOM of machinery including cost blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification (P 178/1.22.8)	mtr	109.90	124.20	Rupees one hundred twenty four and paise twenty only

EXECUTIVE ENGINEER-4
Signature of the Engineer
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.